# BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

## DRAFT TENDER SCHEDULE

**Issued to :** **Original / Duplicate**

**Name of Work :Improvements to Roads and Drains at Doddabommasandra Old Village, Subbanna Beedi and Surrounding areas in ward No 10 Doddabommasandra.**

| Sl. No. | Quantity. | Description | Unit | Rates In Figures | Rates In Words |
|---|---|---|---|---|---|
| 1 | 1097.81 | KSRRB 300-3. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil invoiving , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification with all lead and left as per directions of engineer in charge of the work. | Cum | 220.40 | Rupees Two Hundred Twenty and Forty Paise Only |
| 2 | 141.37 | Removing And Refixing stone slabs of drains and pointing in C.M (1:3) with all lead and left as per directions of engineer in charge of the work. | Sqm | 111.30 | Rupees One Hundred Eleven and Thirty Paise Only |
| 3 | 462.95 | KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. with all lead and left as per directions of engineer in charge of the work. | Cum | 5509.33 | Rupees Five Thousand Five Hundred Nine and Thirty Three Paise Only |
| 4 | 7.49 | Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed,concrete laid in layers not exceeding 15 cms. thick, well compacted, for coping. Including cost of all materials, labour, HOM of machinery, curing complete as per specifications. with all lead and left as per directions of engineer in charge of the work. | Cum | 5695.35 | Rupees Five Thousand Six Hundred Ninety Five and Thirty Five Paise Only |
| 5 | 91.07 | Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specificationsdo- Wall & bottom thickness 15cm with all lead and left as per directions of engineer in charge of the work. | Cum | 7189.42 | Rupees Seven Thousand One Hundred Eighty Nine and Forty Two Paise Only' |
| 6 | 8.90 | Providing and laying reinforced cement concrete pipe NP2 for culverts including pointing ends, and fixing collars with cement mortar 1:2 including cost of all materials, labour, curing complete as per specifications. Specifications. No, KSRB 1000, 2300 MOST Specification No.1000 / 2300 - - 600mm dia with all lead and left as per directions of engineer in charge of the work. | Mtr | 2288.54 | Rupees Two Thousand Two Hundred Eighty Eight and Fifty Four Paise Only |

E.E. (BTP. DIV)

| | Quantity. | Description | Unit | Rates In Figures | Rates In Words |
|---|---|---|---|---|---|
| 7 | 6.62 | KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C workincluding straightening, cutting, bending, hooking, placing in position,lapping and / or welding wherever required, tying with binding wire andanchoring to the adjoining members wherever necessary complete asper design (laps, hooks and wastage shall not be measured and paid)cost of materials, labour, HOM of machinery complete as perspecifications. with all lead and left as per directions of engineer in charge of the work. | Tonne | 72326.98 | Rupees Seventy Two Thousand Three Hundred Twenty Six and Ninety Eight Paise Only |
| 8 | 173.99 | Providing and fixing Precast RCC cover slabs of 100 mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement and pointing for joints 1:3 cement mortor including form work, lift charges,curing and concrtee finished surface on both sides etc,and complete as per the directions of Enginner in charges. | Sqm | 2337.00 | Rupees Two Thousand Three Hundred Thirty Seven Only |
| 9 | 29.25 | Providing and fixing Precast RCC slab of 250mm thick for Culverts made of Plain/Reinforced Cement Concrete design mix M25 with OPC@340kgs,with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregates@0.47cum,with superplasticizer@3lts confirming to 189103-1999 Reaffirmed-2008,Open Foundation complete as per Drawing and Technical Specification including cost of all materials, labour,HOM curing,form works,scaffolding and centering complete as per specifications and pointing for ljoints 1:3 cement mortar including form work,lift charges,curing and concrete finished surfaces on both sides etc,complete and as per the directions of Engineer in-Charge. | Sqm | 5418.00 | Rupees Five Thousand Four Hundred Eighteen Only |
| 10 | 477.86 | KSRRB M200-24. Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials stacking serviceable and unserviceable materials seperately complete as per specifications. with all lead and left as per directions of engineer in charge of the work. | Cum | 952.94 | Rupees Nine Hundred Fifty Two and Ninety Four Paise Only |
| 11 | 2833.15 | KSRRB 300-Compaction KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications .with all lead and left as per directions of engineer in charge of the work. | Sqm | 6.36 | Rupees Six and Thirty Six Paise Only |
| 12 | 424.97 | KSRRB M400- Wet Mix Macadam KSRRB M400-17. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. with all lead and left as per directions of engineer in charge of the work. | Cum | 2001.28 | Rupees Two Thousand One and Twenty Eight Paise Only |

| | Quantity. | Description | Unit | Rates In Figures | Rates In Words |
|---|---|---|---|---|---|
| 13 | 454.32 | Cement concrete pavement.Construction of un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with OPC cement or any other type as per clause 1051.2.2 design mix M20/M30 , with 25mm and down size graded granite metal coarse aggregates and fine aggregtes , with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008 , mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications. - M30 (at 360Kg per cum coarse aggregate @ 0.69cum and fine aggregate @ 0.46cum) with all lead and left as per directions of engineer in charge of the work. | Cum | 5354.02 | Rupees Five Thousand Three Hundred Fifty Four and Two Paise Only |
| 14 | 3028.78 | Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and left as per directions of engineer in charge of the work. | Sqm | 72.08 | Rupees Seventy Two and Eight Paise Only |

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

**Note:**

1. Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
2. Unit rates and prices shall be quoted by the Tender in Indian rupees.
3. Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4. Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))